



Z:\PROJECTS\13690 - Bridge It - Lakes Pedestrian Bridge\CAD\Lakes Pedestrian Bridge.dwg



## GENERAL NOTES:

Manufacturer of prestress concrete slabs to provide shop drawings for design engineers approval prior to construction. Manufacture in accordance with NZS 3109:1997 (precast units)

Concrete strength at 28 daysPrecast units - min 50MPa

Concrete cover

Slab - 35mm (min)Abutment - 50mm (min)

Reinforcement steel in accordance with NZS 3422 AND NZS 3402 HD = grade 500E deformed bar HR = grade 500E plain bar and mesh grade 500E surface finishes to NZS 3114:1987 formed surface - F4 finish and trowelled surface - U5 finish

note brushing direction.

