



- NOTES:**
- LEVELS ARE IN TERMS OF THE MOTURIKI DATUM.
 - COORDINATES ARE IN TERMS OF BAY OF PLENTY 2000 CIRCUIT.
 - ORIGIN OF LEVELS TCC BENCHMARK BM 1142 RL 35.645m.
 - METHOD OF SURVEY: GPS
 - ALL WORKS WERE CARRIED OUT TO TCC IDC 2011 STANDARDS.
 - ALL WASTEWATER MAINS ARE 150mm uPVC PIPES UNLESS SHOWN OTHERWISE.
 - ALL WASTEWATER MAINS ARE SN16 UNLESS SHOWN OTHERWISE.
 - ALL STORMWATER AND WASTEWATER CONNECTIONS ARE 100mm NB uPVC, UNLESS UNDER CARRIAGEWAY WHERE 150mm NB uPVC ARE USED.
 - WASTEWATER CONNECTIONS FOR LOT 702-730 ARE 150mm NB uPVC
 - ALL MANHOLES ARE 1050mm DIA UNLESS OTHERWISE SHOWN.
 - ALL DEEP DRAINAGE CONNECTIONS ARE RAMPED UP TO WITHIN 1.5m OF SURFACE.
 - ALL BURIED AS BUILT INFORMATION SUPPLIED BY HIGGINS CONTRACTORS LTD.

- LEGEND:**
- AS BUILT WASTEWATER
 - EXISTING WASTEWATER
 - AS BUILT WASTEWATER CONNECTION
 - AS BUILT MANHOLE
 - EXISTING MANHOLE
 - AS BUILT RODDING EYE
 - FLOW DIRECTION

ORIGINATOR:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:
PSJ	06.06.18		06.06.18		06.06.18		06.06.18		06.06.18
DRAWN:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:
PSJ	06.06.18		06.06.18		06.06.18		06.06.18		06.06.18
CHECKED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:
GPR	10.07.18		10.07.18		10.07.18		10.07.18		10.07.18
APPROVED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:	SIGNED:	DATE:
GPR	12.06.18		10.07.18		10.07.18		10.07.18		10.07.18

LOT BY: PSJ
PLOT DATE: 11.07.18
SURVEY BY: RXD
SURVEY DATE:

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
ISO 9001 QUALITY ASSURED

HG
TAURANGA OFFICE
LEVEL 1, 60 SPRING STREET
TAURANGA 3110
T +64 7 578 0023
W www.harrisonjones.com

PROJECT: **Summit**
THE LAKES (2012) LIMITED, TAURANGA

TITLE: **STAGE 3JKL CIVILS
WASTEWATER RETICULATION AS BUILT PLAN
SHEET 3
TCC IP 101861**

ISSUE STATUS: **FINAL AS BUILT**

PROJECT No: 1510-141209-01
DRAWING No: 141209-AB203

SCALE: 1:625 - A1
1:1250 - A3

REV: **C**