



NOTES:

1. LEVELS ARE IN TERMS OF THE MOTURIKI DATUM.
2. COORDINATES ARE IN TERMS OF BAY OF PLENTY 2000 CIRCUIT.
3. MAJOR CONTOURS ARE SHOWN AT 1m INTERVALS.
4. MINOR CONTOURS ARE SHOWN AT 0.2m INTERVALS.
5. ORIGIN OF LEVELS TCC BENCHMARK BM 1343 RL 57.59m.
6. METHOD OF SURVEY: GPS
7. ALL WORKS WERE CARRIED OUT TO TCC IDC 2011 STANDARDS.
8. ALL MANHOLES ARE 1050mm DIA UNLESS OTHERWISE SHOWN.
9. ALL STORMWATER PIPES ARE RCRRJ PIPES UNLESS OTHERWISE STATED.
10. ALL CONCRETE PIPES ARE CLASS 2 UNLESS OTHERWISE STATED.
11. ALL BURIED AS BUILT INFORMATION SUPPLIED BY HIGGINS CONTRACTORS LTD.

LEGEND:

- ASBUILT CONTOURS - MAJOR
- ASBUILT CONTOURS - MINOR
- AS BUILT STORMWATER LINE
- AS BUILT SUBSOIL
- PERMANENT WATER LEVEL - 29.30m
- NANAKO STREAM
- AS BUILT MANHOLE
- AS BUILT HEADWALL
- EMERGENCY SPILLWAY
- 'RIVERLEA GOLD' EXPOSED AGGREGATE CONCRETE
- RIPRAP
- WALKING TRACK
- 'RAPIDS' BOULDERS

ORIGINATOR:	TCH	DATE:	18.01.18	SIGNED:		PLOT BY:	TRS
DRAWN:	TRS	DATE:	18.01.18	SIGNED:		PLOT DATE:	19.01.18
C	FINAL AS BUILT	TCH	19.01.18	CHECKED:		SURVEY BY:	
B	FINAL AS BUILT	TCH	19.01.18	CHECKED:		SURVEY DATE:	
A	DRAFT AS BUILT	TCH	18.01.18	APPROVED:			
REF	REVISIONS	BY	DATE	GPR	19.01.18		

ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
 ISO 9001 QUALITY ASSURED
 THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.

HG
 TAURANGA OFFICE
 LEVEL 1, 60 SPRING STREET
 TAURANGA 3110
 T +64 7 578 0023
 W www.harrisongrierson.com

PROJECT: **Summit**
 THE LAKES (2012) LIMITED

TITLE: **STAGE 31**
POND 2 AS BUILT LAYOUT PLAN
 TCC IP 101782

ISSUE STATUS:		FINAL AS BUILT	
PROJECT No:	1520-139618-01	SCALE:	1:250 - A1 1:500 - A3
DRAWING No:	135952-AB401	REV	C