



LEGEND:

- AS BUILT WASTEWATER
- R — AS BUILT RISING MAIN
- - - EXISTING WASTEWATER
- AS BUILT WASTEWATER CONNECTION
- AS BUILT MANHOLE
- EXISTING MANHOLE
- AS BUILT RODDING EYE
- FLOW DIRECTION

NOTES:

1. LEVELS ARE IN TERMS OF THE MOTURIKI DATUM.
2. COORDINATES ARE IN TERMS OF BAY OF PLENTY 2000 CIRCUIT.
3. ORIGIN OF LEVELS TCC BENCHMARK BM 1343 RL 57.59m.
4. METHOD OF SURVEY: GPS
5. ALL WORKS WERE CARRIED OUT TO TCC IDC 2011 STANDARDS.
6. ALL WASTEWATER MAINS ARE 150mm uPVC PIPES UNLESS SHOWN OTHERWISE.
7. ALL WASTEWATER MAINS ARE SN16 UNLESS SHOWN OTHERWISE.
8. ALL STORMWATER AND WASTEWATER CONNECTIONS ARE 100mm NB uPVC, UNLESS UNDER CARRIAGEWAY WHERE 150mm NB uPVC ARE USED.
9. ALL MANHOLES ARE 1050mm DIA UNLESS OTHERWISE SHOWN.
10. ALL DEEP DRAINAGE CONNECTIONS ARE RAMPED UP TO WITHIN 1.5m OF SURFACE.
11. ALL BURIED AS BUILT INFORMATION SUPPLIED BY HIGGINS CONTRACTORS LTD.

ORIGINATOR:	TCH	DATE:	22.12.17	SIGNED:		PLOT BY:	TRS
DRAWN:	PSJ	DATE:	22.12.17	SIGNED:		PLOT DATE:	18.01.18
CHECKED:	TCH	DATE:	18.01.18	SIGNED:		SURVEY BY:	
APPROVED:	TCH	DATE:	22.12.17	SIGNED:		SURVEY DATE:	
BY	DATE	GPR	18.01.18	SIGNED:			

ISO 9001 QUALITY ASSURED	ASSOCIATION OF CONSULTING ENGINEERS NEW ZEALAND
THIS DRAWING AND DESIGN REMAINS THE PROPERTY OF, AND MAY NOT BE REPRODUCED OR ALTERED, WITHOUT THE WRITTEN PERMISSION OF HARRISON GRIERSON CONSULTANTS LIMITED. NO LIABILITY SHALL BE ACCEPTED FOR UNAUTHORISED USE OF THIS DRAWING.	

TAURANGA OFFICE
LEVEL 1, 60 SPRING STREET
TAURANGA 3110
T +64 7 578 0023
W www.harrisongrierson.com

PROJECT:

Summit
THE LAKES (2012) LIMITED

TITLE:

STAGE 3I
WASTEWATER RETICULATION AS BUILT PLAN
SHEET 1
TCC IP 101782

ISSUE STATUS:		FINAL AS BUILT	
PROJECT No:	1520-139618-01	SCALE:	1:500 - A1 1:1000 - A3
DRAWING No:	139618-AB201	REV	B